Agenda Item: 10.

MEMORANDUM

TO:

Programs, Projects and Operations Subcommittee

FROM:

Martin P. Cleveland, Construction Engineer

SUBJECT:

Silver Creek Watershed Structure #14 Stabilization Project

Bids

DATE:

November 22, 2011

Attached are location map, typical cross-section and photographs for the referenced project site. Silver Creek Watershed Structure #14 is located northwest of Tekamah in Burt County. This structure (earthen dam) was built in 2001 to stabilize an eroding gully in the Silver Creek Watershed. The stabilization project work consists of placing rock rip-rap along the eroding front berm of the referenced structure to stop the berm erosion that will eventually endanger the dam's safety. The berm erosion is caused by the pond wave action on the berm. The work includes the furnishing of the labor, materials, equipment, tools and incidentals necessary to install approximately 450 tons of rock riprap and 170 cubic yards of soil infill along approximately 350 feet of dam front berm. The contract provides for 20 working days to complete the project.

A bid summary is attached for your consideration. The apparent low bidder is Glup Construction Inc. with a bid as follows:

- 1. Rock Ripap 450 tons (estimated) at \$57.55/ton with total cost of \$25,897.50
- 2. Soil Infill 170 cubic yards (estimated) at \$10.00/cubic yard with a total cost of \$1,700.00
- 3. Fence 100 ft. (estimated) at \$10/ ft. with a total cost of \$1,000.00
- 4. Grand Total (1+2+3) = \$28,597.50

Based on the estimated quantities, the total project cost would be \$28,597.50. The Engineer's opinion of cost is \$27,000.

This work will be funded via funds included in the Project Maintenance Dams Contract Work (Account 590-4479). As of October 31, 2011 the remaining funds in this account was \$85,412.

It is Management's recommendation that the Subcommittee recommend to the Board of Directors that the General Manager be authorized to execute a contract for Silver Creek Watershed Structure #14 Stabilization Project with Glup Construction Inc., for their total base bid of \$28,597.50.

File: SC15


Summary of Bid Proposals							
Project: Silver Creek Watershed Structure #14 Stabilization Project Opening Date: November 22, 2011				NRD Project No. 504A Opening Time: 11:00 a.m.			
Bidder Name:	1	2	3	4	5	6	
	Japp Bros.	Glup Construction	JMN Construction				
Riprap (450 Tons) Unit Price Bid (\$/Ton)	\$78.81	\$57.55	\$79.00				
2. Soil infill (170 cubic yards) (\$ /cu. Yd.)	\$18.77	\$10.00	\$22.00				
3. Barbed wire fence (100 ft.) (\$/ft.)	\$7.11	\$10.00	\$3.00				
4. Total Base Bid (1 thru 3)	\$39,366.40	\$28,597.50	\$39,590.00				
Rock Supplier	Martin Marietta	Martin Marietta	Martin Marietta				


^{*}Apparent Low Bidder is Glup Construction Inc.


Engineer's Estimate:

\$27,000.00

41111 MC:pb file 504A







DRAINAGE AREA MAP Sec 28; T22N; R10E

Location: 5.5 miles north and 3 miles west of Tekamah, Nebraska.

Location Map




8901 S. 154th St. Omaha, NE 68138-3621 www.papionrd.org TITLE

SILVER CREEK WATERSHED STRUCTURE # 14 BERM PROTECTION PROJECT

Not to scale

DATE: 5/17/2011 Sheet 1 of 3:



Plan Map




8901 S. 154th St. Omaha, NE 68138-3621 www.papionrd.org


TITLE

SILVER CREEK WATERSHED STRUCTURE # 14 BERM PROTECTION PROJECT

Not to scale


DATE: 5/17/2011 Sheet 2 of 3





PROPOSED ROCK RIPRAP CROSS SECTION A-A

Note: Soil Infill Layer top surface will be 0.5 ft. above the top of riprap (elevation 1191 MSL)



Cross-sections



